# ROUGH GRADING PLAN

ROLLING VALLEY PCL A SEC 8B SPRINGFIELD STATION HOA SPRINGFIELD, VA 22153

# OWNER/APPLICANT

SPRINGFIELD STATION HOMEOWNER'S ASSOCIATION, INC.
ATTN: JOHN GIULIANI
8841 APPLECROSS LANE
SPRINGFIELD, VIRGINIA 22153
jngiuliani@cox.net

## CIVIL ENGINEER



DEMARR ENGINEERING, PLLC 7115 LEESBURG PIKE, STE. 215 FALLS CHURCH, VIRGINIA 22043 (703) 214-0975 blake@demarr-engr.com

VICINITY MAP

SCALE: 1" = 1,000'



SOIL ID NUMBERS	SOIL SERIES NAME	FOUNDATION SUPPORT	SOIL DRAINAGE	EROSION POTENTIAL	PROBLEM CLASS
4 <i>C</i>	BARKER CROSSROADS - NATHALIE COMPLEX	FAIR	GOOD	HIGH	IVB
4D	BARKER CROSSROADS - NATHALIE COMPLEX	FAIR	GOOD	HIGH	IVB
108B	WHEATON - SUMERDUCK COMPLEX	MARGINAL	POOR	MEDIUM	IVB

### GENERAL NOTES

1. APPLICANT:

JOHN GIULIANI SPRINGFIELD STATION HOMEOWNER'S ASSOCIATION 8841 APPLECROSS LANE SPRINGFIELD, VA 22153

- 2. THE PROPERTY SHOWN HEREON IS DESIGNATED BY FAIRFAX COUNTY, VIRGINIA, AS TAX MAP REFERENCE NUMBER 0893-06-A, ZONED R-3C (RESIDENTIAL W/ CLUSTER DEVELOPMENT, 3 DU/AC).
- 3. THE PROPERTY SHOWN HEREON IS CURRENTLY IN THE NAME OF SPRINGFIELD STATION HOMEOWNER'S ASSOCIATION, INC. BY DEED RECORDED IN DEED BOOK 03409 AT PAGE 0664 AMONG THE LAND RECORDS OF FAIRFAX COUNTY, VIRGINIA.
- 4. TOTAL AREA OF THE PROPERTY IS 78,583 S.F. OR 1.804 AC.
- 5. SURVEY INFORMATION IS BASED ON FAIRFAX COUNTY GIS RECORDS.
- 6. THE FEMA FLOOD INSURANCE RATE MAP FOR FAIRFAX COUNTY, VIRGINIA, MAP NUMBER 51059C0290E EFFECTIVE DATE SEPTEMBER 17, 2010 DESIGNATES THE PROPERTY AS ZONE X, AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN.
- 7. EXISTING ZONE: R-3C (RESIDENTIAL W/ CLUSTER DEVELOPMENT, 3 DU/AC).
- 8. PUBLIC WATER IS NOT AVAILABLE TO THE PROPERTY. PUBLIC SEWER IS AVAILABLE TO THE PROPERTY.
- 9. THE PROPERTY IS LOCATED IN THE POHICK CREEK WATERSHED.
- 10. THIS DEVELOPMENT SHALL CONFORM TO THE PROVISIONS OF APPLICABLE ORDINANCES, REGULATIONS, AND ADOPTED STANDARDS AS NOTED HEREIN.
- 11. THIS PLAN HONORS ALL EXISTING AND NATURAL DRAINAGE DIVIDES.

	SHEET INDEX
SHEET #	SHEET TITLE
CIV001	COVER SHEET
CIV100	EXISTING CONDITIONS AND DEMOLITION PLAN
CIV200	SITE, EROSION & SEDIMENT CONTROL PLAN
CIV210	OUTFALL ANALYSIS
CIV310	EROSION & SEDIMENT CONTROL NOTES & DETAILS

DEMARR ENGINEERING, PLLC

DEMARR ENGINEERING, PLLC 7115 LEESBURG PIKE, STE 215 FALLS CHURCH, VA 22043 BLAKE D. DEMARR, PE (703) 214-7220 PHONE

PROFESSIONAL SEAL

04/16/20
PROGRESS SET:
NOT FOR
SUBMITTAL OR
CONSTRUCTION

COVER SHEET

PROJECT NUMBER: 19073.01

VALLEY PCL A SEC 8B FIELD STATION HOA IGFIELD, VA 22153


DATE: 04/16/20
DESIGNED: JAK
DRAFTED: JAK


AS NOTED

SHEET NUMBER:

VERIFIED:

CIV001 Cover Sheet, 4/16/2020 8:31:03 AM, ARCH full bleed D (24.00 × 36.00 Ir





### PRE-DEVELOPMENT CONDITIONS NARRATIVE

THE SITE IS LOCATED IN THE SOUTHEAST PORTION OF FAIRFAX COUNTY. THE 1.804-ACRE SITE CONSISTS OF TWO ASPHALT SPORT COURTS AND AN ASPHALT PATH. A TOTAL OF 0.531 ACRES WILL BE DISTURBED DURING CONSTRUCTION.

### **OUTFALL ANALYSIS**

THE PROPOSED SITE WILL HONOR EXISTING DRAINAGE DIVIDES. RUNOFF ALONG THE PROPERTY FLOWS SOUTHEAST TOWARDS ARLEY DRIVE RIGHT-OF-WAY.

THE RUNOFF FROM THE DISTURBED AREA EXITS THE DISTURBED AREA IN A SHEET FLOW CONDITION. THE PROJECT IS PROPOSING A DECREASE IN THE 10-YEAR STORM RUNOFF TO THE OUTFALL. THE SITE CAN CONTINUE TO RUNOFF INTO NEIGHBORING AND DOWNSTREAM SITES BECAUSE THERE IS A NO INCREASE IN RUNOFF AND THE FLOW IS NOT IN A CONCENTRATED FORM.

THERE IS AN YARD INLET ON THE SITE AND CURB INLETS ALONG ARLEY DRIVE, TO CAPTURE THE STORMWATER RUNOFF, SEE STORMWATER INLET MAP ON THIS SHEET. THE STORMWATER IS THEN CONVEYED TOWARD MIDDLE RUN.

IT IS THE OPINION OF THE CONSULTANT THAT THE RUNOFF FROM THE PROJECT SITE WILL NOT CAUSE FURTHER EROSION, SEDIMENTATION, OR FLOODING TO DOWN-GRADIENT PROPERTIES OR RESOURCES, THUS PER SECTION 124-4-4(E), ADEQUATE OUTFALL IS ACHIEVED.

### STORMWATER RUNOFF CALCULATIONS

TOTAL SITE AREA = 1.80 AC. 0.49 AC. EXISTING IMPERVIOUS AREA = EXISTING IMPERVIOUS AREA TO BE REMOVED = 0.10 AC. PROPOSED IMPERVIOUS AREA = 0.39 AC. TOTAL DECREASE IN IMPERVIOUS AREA = 0.10 AC.

### WEIGHTED "C" FACTOR CALCULATIONS:

"C" PRE-DEVELOPMENT =  $(1.31 \times 0.30) + (0.49 \times 0.90) / 1.80 = 0.46$ "C" POST-DEVELOPMENT =  $(1.41 \times 0.30) + (0.39 \times 0.90) / 1.80 = 0.43$ 

### PRE-DEVELOPMENT PEAK DISCHARGES (Tc = 5 MIN, PLATE 2B-6): PEAK Q2 PRE-DEV = $(0.46) \times (5.23 \text{ IN/HR}) \times (1.8 \text{ AC}) = 4.3 \text{ CFS}$

PEAK Q10 PRE-DEV =  $(0.46) \times (6.77 \text{ IN/HR}) \times (1.8 \text{ AC}) = 5.6 \text{ CFS}$ PEAK Q100 PRE-DEV =  $(0.46) \times (9.10 \text{ IN/HR}) \times (1.8 \text{ AC}) = 7.5 \text{ CFS}$ 


### POST-DEVELOPMENT PEAK DISCHARGES (Tc = 5 MIN, PLATE 2B-6):

PEAK Q2 POST-DEV =  $(0.43) \times (5.23 \text{ IN/HR}) \times (1.8 \text{ AC}) = 4.0 \text{ CFS}$ PEAK Q10 POST-DEV =  $(0.43) \times (6.77 \text{ IN/HR}) \times (1.8 \text{ AC}) = 5.2 \text{ CFS}$ PEAK Q100 POST-DEV =  $(0.43) \times (9.10 \text{ IN/HR}) \times (1.8 \text{ AC}) = 7.0 \text{ CFS}$ 

**Q2 DECREASE** = 0.3 CFS Q10 DECREASE = 0.4 CFS **Q100 DECREASE** = 0.5 CFS


### **CHESAPEAKE BAY MAP**

(NOT TO SCALE)




### **OUTFALL MAP**

SCALE: 1" = 200'



### STORMWATER INLET MAP



DEMARR ENGINEERING, PLLC 7115 LEESBURG PIKE, STE 215 FALLS CHURCH, VA 22043 BLAKE D. DEMARR, PE (703) 214-7220 PHONE blake@demarr-engr.com EMAIL

PROFESSIONAL SEAL

04/16/20 PROGRESS SET: **NOT FOR SUBMITTAL OR** CONSTRUCTION

PROJECT NUMBER:

04/16/20 DESIGNED: JAK

BDD AS SHOWN

SHEET NUMBER: CIV210

- 1. SYNTHETIC FILTER FABRIC SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER OR ETHYLENE YARN AND SHALL BE CERTIFIED BY THE MANUFACTURER OR SUPPLIER AS CONFORMING TO THE REQUIREMENTS NOTED IN TABLE 3.05-B.
- 2. SYNTHETIC FILTER FABRIC SHALL CONTAIN ULTRAVIOLET RAY INHIBITORS AND STABILIZERS TO PROVIDE A MINIMUM OF SIX MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF 0° F TO 120° F.
- 3. IF WOODEN STAKES ARE UTILIZED FOR SILT FENCE CONSTRUCTION, THEY MUST HAVE A DIAMETER OF 2 INCHES WHEN OAK IS USED AND 4 INCHES WHEN PINE IS USED. WOODEN STAKES MUST HAVE A MINIMUM LENGTH OF 5 FEET.
- 4. IF STEEL POSTS (STANDARD "U" OR "T" SECTION) ARE UTILIZED FOR SILT FENCE CONSTRUCTION, THEY MUST HAVE A MINIMUM WEIGHT OF 1.33 POUNDS PER LINEAR FOOT AND SHALL HAVE A MINIMUM LENGTH OF 5
- 5. WIRE FENCE REINFORCEMENT FOR SILT FENCES USING STANDARD-STRENGTH FILTER CLOTH SHALL BE A MINIMUM OF 14 GAUGE AND SHALL HAVE A MAXIMUM MESH SPACING OF 6 INCHES.

### INSTALLATION

- 1. THE HEIGHT OF A SILT FENCE SHALL BE A MINIMUM OF 16 INCHES ABOVE THE ORIGINAL GROUND SURFACE AND SHALL NOT EXCEED 34 INCHES ABOVE GROUND ELEVATION.
- 2. THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE UNAVOIDABLE, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED.
- 3. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4-INCHES WIDE AND 4-INCHES DEEP ON THE UPSLOPE SIDE OF THE PROPOSED LOCATION OF THE MEASURE.
- 4. WHEN WIRE SUPPORT IS USED, STANDARD-STRENGTH FILTER CLOTH MAY BE USED. POSTS FOR THIS TYPE OF INSTALLATION SHALL BE PLACED A MAXIMUM OF 10-FEET APART (SEE PLATE 3.05-1). THE WIRE MESH FENCE MUST BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST ONE INCH LONG, TIE WIRES OR HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF TWO INCHES AND SHALL NOT EXTEND MORE THAN 34 INCHES ABOVE THE ORIGINAL GROUND SURFACE. THE STANDARD-STRENGTH FABRIC SHALL BE STAPLED OR WIRED TO THE WIRE FENCE, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.
- 5. WHEN WIRE SUPPORT IS NOT USED, EXTRA-STRENGTH FILTER CLOTH SHALL BE USED. POSTS FOR THIS TYPE OF FABRIC SHALL BE PLACED A MAXIMUM OF 6-FEET APART (SEE PLATE 3.05-2). THE FILTER FABRIC SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING ONE INCH LONG (MINIMUM) HEAVY-DUTY WIRE STAPLES OR TIE WIRES AND EIGHT INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT BE STAPLED TO EXISTING TREES. THIS METHOD OF INSTALLATION HAS BEEN FOUND TO BE MORE COMMONPLACE THAN #4.
- 6. IF A SILT FENCE IS TO BE CONSTRUCTED ACROSS A DITCH LINE OR SWALE, THE MEASURE MUST BE OF SUFFICIENT LENGTH TO ELIMINATE ENDFLOW, AND THE PLAN CONFIGURATION SHALL RESEMBLE AN ARC OR HORSESHOE WITH THE ENDS ORIENTED UPSLOPE (SEE PLATE 3.05-2). EXTRA-STRENGTH FILTER FABRIC SHALL BE USED FOR THIS APPLICATION WITH A MAXIMUM 3-FOOT SPACING OF POSTS.
- 7. ALL OTHER INSTALLATION REQUIREMENTS NOTED IN #5 APPLY.
- 8. THE 4-INCH BY 4-INCH TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC.
- 9. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.

### **MAINTENANCE**

- 1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- 2. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM END RUNS AND UNDERCUTTING.
- 3. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY. THE FABRIC SHALL BE REPLACED PROMPTLY.
- 4. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
- 5. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED AND SEEDED.

### **DUST CONTROL**

REFER TO STANDARD AND SPECIFICATION 3.39 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.

### **GENERAL LAND CONSERVATION NOTES**

- 1. NO DISTURBED AREA WHICH IS NOT ACTIVELY BEING WORKED SHALL REMAIN DENUDED FOR MORE THAN 14 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR.
- 2. ALL E&S CONTROL MEASURES APPROVED WITH THE PHASE ONE E&S CONTROL PLAN SHALL BE PLACED AS THE FIRST STEP IN GRADING.
- 3. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS SHALL BE SEEDED AND MULCHED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY (AS SOON AS POSSIBLE BUT NO LATER THAN 48 HOURS) AFTER COMPLETION OF GRADING. STRAW OR HAY MULCH IS REQUIRED. ALL SOIL STOCKPILES SHALL BE SEEDED AND MULCHED WITHIN 14 DAYS AFTER GRADING.
- 4. ANY DISTURBED AREA NOT COVERED BY § 11-0406.1 AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
- 5. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE

### **TEMPORARY SEEDING NOTES**

WHERE ROUGH-GRADED AREAS WILL NOT BE BROUGHT TO FINAL GRADE FOR A PERIOD OF MORE THAN 7 DAYS, TEMPORARY SEEDING SHALL APPLY. REFER TO STANDARD AND SPECIFICATION 3.31 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.

ACCEPTABLE TEMPORARY SEEDING PLANT MATERIALS						
"QUICK REFERENCE FOR ALL REGIONS"						
Planting Dates	<u>Species</u>	Rate (lbs./acre)				
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (Lolium multi-florum) & Cereal (Winter) Rye (Secale cereale)	50 - 100				
Feb. 16 - Apr. 30	Annual Ryegrass (Lolium multi-florum)	60 - 100				
May 1 - Aug 31	German Millet (Setaria italica)	50				

Source: Va. DSWC


### PERMANENT SEEDING NOTES

PERMANENT VEGETATIVE COVER SHALL BE APPLIED TO AREAS THAT WILL BE LEFT DORMANT FOR A PERIOD OF MORE THAN 1 YEAR. REFER TO STANDARD AND SPECIFICATION 3.32 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.


### **TABLE 3.32-D** SITE SPECIFIC SEEDING MIXTURES FOR PIEDMONT AREA Total Lbs. Per Acre Minimum Care Lawn 175-200 lbs. - Commercial or Residential 95-100% - Kentucky 31 or Turf-Type Tall Fescue - Improved Perennial Ryegrass 0-5% 0-5% - Kentucky Bluegrass 200-250 lbs. High-Maintenance Lawn 100% - Kentucky 31 or Turf-Type Tall Fescue General Slope (3:1 or less) 128 lbs. - Kentucky 31 Fescue 2 lbs. - Red Top Grass - Seasonal Nurse Crop \* 20 lbs. 150 lbs. Low-Maintenance Slope (Steeper than 3:1) 108 lbs. - Kentucky 31 Fescue - Red Top Grass 2 lbs. - Seasonal Nurse Crop \* 20 lbs. - Crownvetch \*\* 20 lbs 150 lbs. \* Use seasonal nurse crop in accordance with seeding dates as stated below: February 16th through April ..... Annual Rye May 1st through August 15th ..... Foxtail Millet August 16th through October . . . . . . . . . . . . Annual Rye November through February 15th . . . . . . . . Winter Rye \*\* Substitute Sericea lespedeza for Crownvetch east of Farmville, Va. (May through September use hulled Sericea, all other periods, use unhulled Sericea). If Flatpea is used in lieu of Crownvetch, increase rate to 30 lbs./acre. All legume seed must be properly inoculated. Weeping Lovegrass may be added to any slope or low-maintenance mix during warmer seeding periods; add 10-20 lbs./acre in

### **GENERAL EROSION AND SEDIMENT CONTROL NOTES**

- ES-1: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS 4VAC50-30 EROSION AND SEDIMENT CONTROL REGULATIONS.
- ES-2: THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- ES-3: ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- ES-4: A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- ES-5: PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.
- ES-6: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- ES-7: ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- ES-8: DURING DEWATERING OPERATIONS. WATER WILL BE PUMPED INTO AN APPROVED FILTERING
- ES-9: THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
- MS 17 EACH CONTRACTOR TO MONITOR THEIR RESPECTIVE CONSTRUCTION VEHICLE ACCESS ROUTE TO MINIMIZE THE TRANSPORT OF SEDIMENT FROM THE SITE ONTO ANY PUBLIC OR PAVED ROADS. ANY SEDIMENT TRACKED ONTO PUBLIC OR PAVED ROADS SHALL BE IMMEDIATELY SWEPT WITH BROOM BY CONTRACTOR WHO TRACKED SEDIMENT ONTO PAVED SURFACE.



### FAIRFAX COUNTY PRIORITY RATING FORM FOR EROSION & SEDIMENT CONTROL



Descriptions on Reverse Side


HIGH

PROJECT PRIORITY LEVEL:

APPROVED BY:

"Reserved for Fairfax County use "

### FAIRFAX COUNTY PUBLIC FACILITIES MANUAL



DEMARR ENGINEERING, PLLC 7115 LEESBURG PIKE, STE 215 FALLS CHURCH, VA 22043 BLAKE D. DEMARR, PE (703) 214-7220 PHONE blake@demarr-engr.com EMAIL

PROFESSIONAL SEAL

04/16/20 PROGRESS SET: NOT FOR **SUBMITTAL OR** CONSTRUCTION

> 0 EROSI( NTROL

PROJECT NUMBER: 19073.01

04/16/20 DESIGNED: DRAFTED: JAK BDD VERIFIED: N.T.S.

S

SHEET NUMBER:

CIV310